



# DAV PUBLIC SCHOOL

CHANDRASEKHARPUR, SAILASHREE VIHAR, BHUBANESWAR  
(Affiliated to C.B.S.E., New Delhi, Affiliation No. 1530044, School No.-15329)

## QUOTATION CALL NOTICE

No.DAV (CSP)/ 1436 /2024

Date. 03.04.2024

Sealed quotations are invited by the undersigned from reputed Agency/contractor for the Interior & Electrical Work of Library Hall at DAV Public School, Campus- II as per drawing. Interested parties may submit their quotations for the purpose as per prescribed profomas placed in the notice board. The sealed quotations should reach the undersigned on or before **10.04.2024** up to **3.00 PM** and will be opened on dt. **10.04.2024** at **04.00 PM**. The quotations received after the stipulated date & time due to postal delay or incomplete in any respect shall not be considered. The quotations without **GST Certificate & PAN** shall not be considered. The envelope containing the quotation must be written as "**Quotation for Interior & Electrical Work of Library Hall at Campus-II**". The undersigned reserves the right to cancel any / all the quotations without assigning any reasons thereof.

## TERMS & CONDITION

1. Rates are to be quoted for execution of the works with supply of material which included transportation, loading, unloading, all taxes applicable.
2. The school authority does not bind to accept the lowest quotation & reserves the right to accept or reject any quotation without assigning any reasons whatsoever.
3. Payment will be made after completion of work and submission of bill.
4. The materials approved by the competent authority only shall be used.
5. The bidders are requested to visit the work site before quoting the price.

  
PRINCIPAL

Memo No. DAV(CSP)/ 1437 /2024

Date: - 03.04.2024

Copy to:-

1. The Notice Board of the School for information of the public / persons concerned on this profession.
2. The Principal of DAV Public School, Unit VIII / Pokhariput / Kalinga Nagar, BBSR,CDA, Sector VI, Gandarpur, Cuttack with a request to kindly take necessary steps to display the tender notice on the school Notice board for information of the person concerned on this profession.
3. The concerned file for record.

  
PRINCIPAL

**MANAGED BY - DAV COLLEGE MANAGING COMMITTEE, CHITRA GUPTA ROAD, DELHI**

At- Chandrasekharpur, Sailashree Vihar, Bhubaneswar- 751021 (Odisha)

Phone No. : 0674-2740651, 2740551, Email: davcspur@gmail.com, Website: www.davcsp.org

**DAV PUBLIC SCHOOL, CHANDRASEKHARPUR-21**

**QUOTATION FORM FOR INTERIOR & ELECTRICAL WORK OF LIBRARY HALL AT  
CAMPUS-II**

Name of the supplier/ Agencies.....

Address .....

Phone No .....

<b>SL N O</b>	<b>PARTICULARS</b>	<b>QTY</b>	<b>PRICE PER UNIT Including GST%</b>
01	<b>FULLY HEIGHT PARTITION (FULLY SOLID)</b> Providing and fixing in position fully solid partition work as per drawing in frame work at 2'x2' grind comprising of 2"x1 1/2" aluminium section.	450 Sft	
02	<b>GYPSUM BOARD CEILING</b> Removing the existing False Ceiling (Gypsum Board) Providing & fixing in position New false ceiling in Gypsum board 12 mm thick for horizontals & Verticals fixed over G.I. frame work as specified by India Gypsum Co. Ltd. including trap doors for A.C. Unit in 18mm thick M. R. Grade Plywood with Stainless Steel hinges & locks with moulding 1"	750 Sft	
03	<b>DOORS-SEMI GLAZED</b> Providing & fabricating fixing door shutter with 28mm x 75mm height & 28mm x 75mm, 28mm x 60mm, 28mm x 80mm rails of well seasoned with necessary polishing etc.	52.50 Sft	
04	<b>VITRIFIED TILE FLOORING</b> Providing and Fixing 600 mm X600 mm polished/unpolished Premium Quality vitrified ties in pattern of approved make/design in hall and other specified areas on existing Terrazzo/Kota flooring/Tiles including 4" skirting to masonry walls and columns, laid with tile adhesive as per manufacturers recommendations. The work includes cleaning/leveling and removal of	650 Sft	
05	<b>DOOR CLOSER</b> Providing and fixing Godrej/Doorset/Dorma make over head door closers in door with necessary fixtures & fittings etc.	02 Nos	
06	<b>FLOOR SPRING</b> Providing & fixing Godrej make heavy duty Floor spring in entrance door with necessary fixtures and fittings etc.	01 Nos	

07	<b>ANTI TERMITE TREATMENT</b> Anti termite treatment with approved chemicals for entire floor area, wall area and hidden wood work.	600 Sft	
08	<b>IN CHARGE'S TABLE</b> Providing and erecting in position, Manager's/officers tables side credenza of size 3'-6"x1'-6"x2'-6" and a front drawer unit consisting of 3 nos of drawer units.		
A	Approx size of 3'-6" x 2'-3" x 2'-6"	01 Nos	
B	Approx size of 4'-0" x 2'-6" x 2'-6"	01 Nos	
09	<b>LOW/FULL HEIGHT STORAGE</b> Providing and fixing of low/full height storage cabinet having 450 mm depth made out of 19 mm thk block board.	475 Sft	
10	<b>PLY BOXING</b> Providing & Fixing ¾ " BWR ply boxing for the rolling shutters / separation for boxing with out laminate finish above false ceiling painted with Enamel paint. Necessary framing shall be provided.	100 Sft	
11	<b>ROLLER BLINDS</b> Providing, fabricating and fixing of column paneling made out of 12mm ply and 1mm thick laminates furnishing with including cost of all labour and materials.	80 Sft	
12	<b>ROUND MODULAR TABLE</b> Providing round modular low standing Study Table of approved make covered with approved fabric with wooden frame work and decorative beading.	08 Nos	
13	<b>WALL PANELLING (WITH LAMINATE)</b> Providing, fabricating and fixing of column paneling made out of 12mm ply and 1mm thick laminates furnishing with including cost of all labour and materials.	350 Sft	
14	<b>WALL PUTTY (WITH POP PUNNING)</b> Providing & applying 2 coats of plastic emulsion paint of royale ICI dulux & approved shade on wall, columns, beams, ceiling etc and back office hall including locker room.	550 Sft	
15	<b>WALL PLASTIC PAINT</b> Providing & applying 2 coats of plastic emulsion paint of royale ICI dulux & approved shade on wall, columns, beams, ceiling etc and back office hall including locker room.	550 Sft	

II	<b>ELECTRICAL WORK</b>		
01	<b>ELECTRICAL WIRING WORK</b> Concealed / resessed / surface light point / fan point / call bell point etc. wiring using 1100V FRLS grade 3R (P+N+E) x 1.5 Sq.mm FRLS multi stranded copper conductor PVC insulated wires (with proper R,Y,B color code) pulled through rigid FR/FRLS PVC conduits of 20mm Dia 1.5 mm thick laid concealed		
A	Primary light points including the cost of clip in type 6A Modular switch of legrand my linc or equivalent.	30 Nos	
B	Independent point using one 6 Amp Modular Switch and one 6 Amp, 2/3 pin Modular socket mounted on a suitable size Box for wall fans.	06 Nos	
C	6 Amp 2/3 pin Modular socket with 6A Modular switch. ( on common switch Board.)	05 Nos	
D	Primary light points including the cost of clip in type 6A Modular switch of legrand mylinc or equivalent make & model as approved by project in charge. ( 1 light controlled by one switch UPS point )	25 Nos	
02	Concealed power point using 16 Amp 3 Pin plug socket with 16 Amp Modular switch of legrand mylinc or equivalent make mounted on separate board using suitable size galvanized iron junction & switch boxes.	01 Nos	
03	Concealed raw power point using 6 Amp, 2/3 Pin Modular plug socket with 6 Amp Modular switch of legrand mylinc or equivalent make on separate board.	02 Nos	
04	<b>COMPUTER WIRING WORK</b> Supply and fixing of concealed UPS power points using 1 nos. of 16 Amp, 3 Pin Modular switches to be provided on table top + 3 nos. 6 Amp Modular socket below table top of legrand	02 Nos	
05	Supply and fixing of concealed UPS power points using clip in modular type 5 No. of 6/16 amp socket points controlled by 2 No of 16 amp modular switch with indicator of legrand my linc	01 Nos	
06	<b>PANEL BOARD &amp; DISTRIBUTION BOARDS.</b> Supply, delivery, installation , testing , commissioning , of L&T indoor wall ,floor , mounted , type distribution boards made out of 2 mm thk. CR sheet metal duely acid treated premised & painted with 2 coats of enamel paint. Incoming- 1No 63A-16ka -4 pole MCCB. 1 set of 63A copper bus bar Out going- 3 Nos 32 A DP MCB 1Nos 32 A DP MCB for Glow sign board 1No. VAF Digital meter with CT. 3 Nos Phase indicator lamps	01 Nos	

07	Supplying & Fixing 63Amp, 415 V Wireable IC Cutout-3nos in MS enclosure with j lock & key arrangements.	01 Nos	
08	<b>C.D.B</b> 8 way SPN DB Incoming 1 No. 32A DP- MCB Out going 6 No. 6-10A SP MCB	01 Nos	
09	<b>U.P.S. INCOMING DB</b> 4 way SPN DB 40 Amp DP-10KA- MCB- 2 No	01 Nos	
10	<b>U.P.S. OUTGOING DB</b> 4 way SPN DB 32Amp DP-10KA- MCB	01 Nos	
11	1200 mm Ceiling Fan	04 Nos	
12	Fan Hook	04 Nos	
13	LED Strip Lights of approved colour	07 Nos	
14	Supply and fixing of 2X36 Watt Light	08 Nos	
15	Supply, installation and testing of LED light fittings (1X15 wt) with angle holder of Philips/ Crompton	45 Nos	
16	450 mm Sweep wall fan	06 Nos	
17	<b>CABLE, MAINS &amp; SUBMAINS.</b> Supply of all required materials and wiring to circuits/ sub mains with following number and sizes of PVC insulated 1100 volt grade multi standard		
A	Recessed wiring with (2Rx2.5sqmm +1Rx1.5sqmm) copper wire ( LDB/RDB to Common Switch board and power Points / UPS points etc )	100 Mtr	
B	Recessed wiring with (2Rx4.0sqmm +1Rx2.5sqmm) copper wire ( UPS input to CDB points )	30 Mtr	
C	Recessed wiring with ( 2Rx6.0 sqmm +1Rx4.0 sqmm ) copper wire ( PANEL to L.D.B / Inverter )	30 Mtr	
18	<b>EARTHING</b> Providing and fixing Earthing with G.I. earth plate 600 mm X 600 mm X 6.36 mm thick including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe of 2.7 metre long etc.	01 Nos	
19	Providing and fixing of Earthing with copper earth plate 600 mm X 600 mm X 3.18 mm thick including accessories, and providing masonry enclosure with cover plate having locking arrangement	01 Nos	
20	Supplying and laying 25 mm X 5 mm G.I strip at 0.50 meter below ground as strip earth electrode, including connection/terminating with G.I. nut, bolt, spring, washer etc.	15 Mtr	
21	Providing and fixing 4.00 mm dia copper wire on surface or in recess for loop earthing as required.	15 Mtr	

22	<b>DATA LAN WORK</b> Supply of all required materials and laying of CAT-6 LAN wiring from server to Hub and Hub to computer I/O Points of approved brand ((D-Link) laid through PVC conduits of 20mm dia laying on wall / ceiling with saddles / Spacer etc. complete as in all respect.	50 Mtr	
23	Supply , fixing of RJ 45 information outlet (I/O) with safety shutter of D-link make with front modular cover plate, flush box metallic or PVC for trucking system etc.	02 Nos	
24	Supply & fixing 6 U wall mounted modem rack with cable manager, cantilever self, fan & mounting kit etc all complete.	01 Nos	
25	Supply & fixing of 24 port PATCH PANEL (Make D-LINK)	01 Nos	
26	Supply & fixing of 24 port Giga Switch (Make D-LINK)	01 Nos	
27	Supply & fixing 1Mtr long E-CAT 6 PATCH Cord (Make D-LINK or Equivalent Make)	05 Nos	
28	Supply & fixing 2Mtr long E-CAT 6 PATCH Cord (Make D-LINK Equivalent Make)	05 Nos	

G S T No.....

PAN No.....

Quotation No.....

Date.....

Signature of Supplier/Agency



Regd. No.-  
CA/2010/48290  
★ SOUBHAGYA NAYAK ASSOCIATES ★  
BHUWANESHWAR

